



An introduction to
DeliveREE



Joe Hayden, Senior Executive Engineer
Emily Clarke, Energy Engineer

October 2022



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 101032833



Section 01

The Vision





CODEMA TEAM



- **Energy Advisers** to Dublin Local Authorities
- Founded in **1997** as **not-for-profit** organisation
- **32 staff** based in Temple Bar





OUR SERVICES



ENERGY MONITORING & MANAGEMENT



ENERGY AWARENESS



ENERGY POLICY & PLANNING



PROJECT MANAGEMENT



MATCH FUNDING



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 696040.



- **Facilitators** of Energy Performance Contracts (10 years' experience)
- Providing **Training** of EnPC Project Facilitators



AGENDA

- 1. The Vision** - Joe (5 mins)
- 2. The Reality** - Emily (10mins)
- 3. Project Pipeline progress** - Emily (5 mins)
- 4. The Learnings** (the challenges and our solutions) - Joe (10 mins)



DELIVEREE PROJECT

Overall Project Aim:

1. Create a **Project Implementation Unit** and **scalable delivery model** that can be replicated across Ireland and Europe

2. Deliver **9 signed** Energy Performance Contracts:
 - Value **€20.4m** (**€10.2** from **private finance**)
 - **3.8 ktCO₂** and 24GWh **savings**
 - Involving over **140** Local Authority Buildings



PROJECT IMPLEMENTATION EXPERIENCE



- **4 x Energy Performance Contracts**
 - ✓ **15** public buildings
 - ✓ **€3,066,000** Capital investment
- **1 x Energy Supply Contract**
 - ✓ Tallaght District Heating System
 - ✓ **€ 7,972,000** Capital investment
- Of the **€11.4m invested**:
 - €4.3m (**38%**) from the **Private** sector via **ESCos**
 - €5.5m (**48%**) from **grants**
 - €1.6m (**14%**) from the **Local Authority**
- Funding arrangement made possible by **Energy Performance Contracting**



 This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 696040.





WHAT'S THE PROBLEM?

Business-as-usual:

- Its **slow**, focus on **single technology** (CHP, Heat Pump, LED.....)
- Results in small, **low value** projects
- Dependent on **building owner finance**
- All **risk** with project owner
- Frequent **cost overrun**
- **Poor results** (no Measurement & Verification) – **Rebound effect**






WHAT'S THE SOLUTION?



DeliveREE:

- **'One stop shop'** Project Implementation Unit
- **Standardises** project development
- **Aggregates** Projects
- Uses **Performance** Contracts
- Facilitates **Private Finance**






DELIVEREE - PIU





DELIVEREE - STRUCTURE



Project Development Structure:

1. Project Identification
2. Standardisation
3. Aggregation
4. Procurement & Finance
5. Contract Management and M&V



DELIVEREE PROJECT PIPELINE



- ❖ We have identified **pipeline of 19 projects.**
- ❖ Includes **140 Local Authority buildings**
- ❖ Estimates CAPEX - **€20.4m**
- ❖ Estimates savings – 29% (**3,977 tCO2**)
- ❖ **Funding** structure: 10-20% project owner, 40-50% grant and 40-50% private financing

Location (area, town...)	Type of investment[1]	Description of the investment	Quantification (Buildings)	Current energy consump-	Energy savings (%)	Renewable energy production	Energy investment costs
DCC	Building Energy Efficiency	Building for new CMP on LED lighting - Civic Office	1	16,620,629	22%	-	1726,866
DCC	Building Energy Efficiency	Smart Lighting Controls for energy efficiency measure	1	4,238,476	26%	-	1587,860
DCC	Building Energy Efficiency	Smart lighting for energy efficiency measure (LED, NP, PV)	20	6,446,617	26%	-	11,626,000
DCC	Building Energy Efficiency	Smart lighting for energy efficiency measure (LED, NP, PV)	6	2,298,864	26%	-	1,891,216
DCC	Building Energy Efficiency	Energy Efficient measure - Smart Mechanical and	2	2,792,787	26%	-	1,245,794
DLR	Building Energy Efficiency	Building for energy efficiency measure - County Hall, Ballinacorney, Markov Lane and	4	7,838,068	45%	-	11,626,662
DLR	Building Energy Efficiency	Smart Controls for Energy Efficient Refurbishment - Meadstown, Leixlip town and	3	6,896,189	26%	-	1,609,000
DLR	Building Energy Efficiency	Smart lighting for energy efficiency measure (LED, NP, PV)	50	9,704,711	16%	-	12,624,211
FCC	Building Energy Efficiency	Building for energy efficiency measure - Sward County Hall, Donagh B Library Building, Clonsilla	3	6,245,421	26%	-	11,704,576
FCC	Building Energy Efficiency	Building for energy efficiency measure (LED, NP, PV)	15	4,670,249	26%	-	1759,000
FCC	Building Energy Efficiency	4th floor building for energy efficient Refurbishment	6	2,106,262	17%	-	116,116
FCC	Electrical/Physical Charge	EV charging hubs installed on the depot in Fingal (2x 500W DC fast chargers and 1x 22kW AC charger)	2	-	-	-	1109,000
SDCC	Building Energy Efficiency	Smart lighting for energy efficient Refurbishment - Clonsilla and	2	6,896,025	26%	-	1,605,000
SDCC	Building Energy Efficiency	Smart lighting for energy efficiency measure including theatre and drama	2	674,085	26%	-	1164,251
SDCC	Building Energy Efficiency	2 Office buildings for energy efficient measure including County Hall and Clonsilla office	2	5,642,651	15%	-	1716,225
SDCC	Building Energy Efficiency	Smart lighting for energy efficiency measure (LED, NP, PV)	15	2,444,242	26%	-	1,239,000
SDCC	Renewable Energy	Photovoltaic solar panels on the roof of the depot in Fingal (2x 500W DC fast chargers and 1x 22kW AC charger)	1	1,465,000	12%	-	115,000
SDCC	Renewable Energy	Photovoltaic solar panels on the roof of the depot in Fingal (2x 500W DC fast chargers and 1x 22kW AC charger)	6	-	-	4,440	11,000,000
SDCC	Electrical/Physical Charge	EV charging hubs installed at 2nd floor	1	-	-	-	1109,000
SDCC	District Heating	SDCC station - to connect Civic Theatre on PPM Group to DCC station	2	965,000	72%	-	1105,271
Totall savings			146	15,503,000	29%	4,440	119,562,262



DELIVEREE - DELIVERY OF RENEWABLE AND ENERGY EFFICIENCY PROJECTS ACROSS THE DUBLIN REGION



Project Partners :

- ❖ Codema
- ❖ Four Dublin Local Authorities
- ❖ Resourceful Futures Ltd (UK)
- ❖ Philip Lee Solicitors Ltd
- ❖ Sustainable Development Capital LLC (SDCL)





DELIVEREE - DELIVERY OF RENEWABLE AND ENERGY EFFICIENCY PROJECTS ACROSS THE DUBLIN REGION



Project Advisory Board:

- ❖ Department of the Environment Climate & Communications (**DCCA**)
- ❖ Department of Public Expenditure and Reform (**DPER**)
- ❖ National Development Finance Agency (**NDFA**)
- ❖ Jožef Stefan Institute (**IJS**) **Slovenia**
- ❖ Sustainable Energy Authority of Ireland (**SEAI**)
- ❖ **Lawler** Sustainability (**ESCo**)
- ❖ Association of Irish Energy Agencies (**AIEA**)
- ❖ Health Service Executive (**HSE**)



Section 02

The Reality





GUIDANCE DOCUMENT

- Output of second work package
- Interviewed 14 EPC experts across Ireland and Europe
- EPC market from communication, risk, technical, procurement, finance and legal angles
- Contract Cheat Sheet developed in response to a lack of shared understanding



Table 1 Contract Cheat Sheet

EPC related term		Standard Works Contract	EnPC
General Terms			
Contract elements	Works	Works only	Included
	Services/Supply	Not included	5-20 years
	Performance Guarantee	Not included	Included
Project complexity	Single technology/low complexity	Used for	Suitable for
	Deep Retrofit		
Distribution of performance risk	Client holds risk	Client holds most to all risk	Client holds minimal risk
	Contractor holds risk	Contractor holds minimal risk	Contractor holds most to all risk
Balance sheet status	On	Mostly on	Depends on Client appetite, contract structure, etc
	Off	Cannot be off balance sheet	
Project Funding	Client	Up to 100%	Up to 100%
	Government Grants	Up to 50%*	Up to 30%*
	Third Party Finance	Not applicable	Up to 100%
Works			
Design and specifications development	Standard	Client develops design pre-procurement	Not suitable for contract/procurement type
	Outcome-based	Not suitable for contract/procurement type	Client specifies outcome, not design
New Equipment ownership	Client owned	In a typical works contract, the Client owns the equipment installed	With compensation to contractor for early termination
Maintenance of existing Equipment	Client	Existing equipment not considered in a standard works contract	Depends on contract - not relevant in ESCs, client or contractor in EPCs
	Contractor		
Testing, Commissioning and Defects responsibilities	Contractor	Contractor tests and commissions, low accountability for defects post-handover	Contractor tests and commissions, incentivised to correct defects throughout supply/service period
Services and Supply			
Services	Throughout contract period	Services not included in contract	5-20 years
Maintenance Responsibilities	New equipment	Services not included in contract	Contractor to maintain & replace Maintenance depends on contract; Client pays for replacement
	Existing equipment		
Handover/re-commissioning responsibilities	Contractor	Services not included in contract	Contractor to perform full re-commissioning and hand over fully operational system



This project has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 101032833





PROTOCOLS AND PROCEDURES

- Output of Work Package 3
- Procedures and protocols for how to develop a project
- Includes standardised template documents

The image shows a project appraisal report for DeliveREE. The cover page is titled "DLR CoCo Buildings EPC Project Appraisal". Below the cover page, there is a table of contents and a table detailing project start-up tasks.

Task ID	Task Description	Dependencies	Required Evidence	Notes/Status
51-P1	Project Start-up			
51-P1-P1	Identify organisation and contact details	Use this link to check if the contacts are already in the database: https://table.codema.com/2b7107616462464f	Complete 51-C1 in 51-P1, P15 Communications Procedure	Complete "Identified Project Form" in database
51-P1-P2	Create folder for site	A google drive folder should be created to store all the documents for the site.	Copy and paste "Template Site Folder" in European Project's Active European Project's Active European Project's Active European L Sites and rename	Link to folder
51-P1-P3	Complete Guest Chart for project until aggregation	Follow the instructions on the Guest Chart template to estimate the timescale and the end of Stage 3a (Aggregation)	Complete "Site" tab of Guest Chart	"Project Guest Chart" (Use "EP - Guest Chart" template)
51-P1-P4	Communications Procedure for Stage 1	The communication plan is a pre-filled document with the minimum communications required for Stage 1 (and every other stage of the project)	Complete 51-P1-P4 Communications Procedure	Editable records for each task in communication plan containing evidence required in communication plan
51-P1-P5	Kick-off Meeting with Client	There is a kick-off meeting agenda and presentation in the template folder. The meeting should address all topics in the agenda and ensure client stakeholders (incl. site managers) is aware of the project and the programme.	Complete 51-C2 in 51-P1, P15 Communications Procedure	"Kick-off Meeting Minutes" (Use "P1 - Meeting Minutes" Word template)
		The initial approval ones includes a kick-off meeting agenda and presentation in the template folder.		"Initial Approval ones" (Use "P1 - Meeting Minutes" Word template)




PROTOCOLS AND PROCEDURES

- Online platform developed by Codema
- Central place to:
 - Understand project development process
 - Access templates
 - Record progress
 - Record communications

The screenshot displays the 'Project Implementation Unit' interface. On the left, a blue navigation menu lists various project stages: '1. Initial data gathering (sites)', '2. Appraisal (Lots)', '3. Procurement (Lots)', 'Communications & evidence', 'Outstanding Tasks', 'Add a new Communication Reco...', 'Internal/non-project Meetings', 'Procedures & milestones', and 'Lot Kanban'. The main content area is divided into two sections. The top section, titled 'Project Implementation Unit / Procedures & milestones', contains a table with columns for 'Name', 'Type', and 'Description'. It lists '1a. Project setup' and '1b. Initial appraisal', both categorized as 'Procedure'. The bottom section, titled 'Project Implementation Unit / 1. Initial data gathering (sites)', shows a table with columns for 'DCC', 'DLR', 'FCC', 'SDCC', and 'All records'. It lists various sites like 'WATERY LANE DEPOT', 'Rush Public Library', and 'Draiocht & Library Building', with associated records and dates. A 'Templates' section at the bottom lists various project templates such as 'T1- Meeting Minutes', 'T2- Meeting Agenda', 'T3- Initial Appraisal Inp', 'T4- Initial Appraisal Pre', 'T5- Risk Assessment (g', 'T6- Risk Assessment (project)', 'T7- Technical File Questionnaire', 'T8- Audit Tender Brief', 'T9- Feasibility Study Report', 'T10- Feasibility Procedure', 'T11- Project Appraisal Inputs', 'T12- Project Appraisal Report', 'T12a- Diagram for Detailed Appraisal Report', and 'T12b- Detailed Appraisal Presentation', each with a 'Template' button.



GAP TO TARGET ANALYSIS



Section 03


The Projects





PROJECTS- DLR ENERGY PERFORMANCE CONTRACT

- **Project Type:** Energy Performance Contract
- **Client:** Dún Laoghaire-Rathdown County Council
- **Project value:** €3.1 million
- **Project scope:**
 - 3 buildings: County Hall, large library, theatre
 - Holistic upgrades including building fabric, heat pump, BMS, LED, Solar PV etc.
- **Project Financing:**
 - 45% Client: 45% Pathfinder funding: 10% ESCo
 - NPV of €400k
 - Payback of 10.5 years






PROJECTS- SDCC ENERGY PERFORMANCE CONTRACT



- **Project Type:** Energy Performance Contract
- **Client:** South Dublin County Council
- **Project value:** €2.5 million
- **Project scope:**
 - 5 buildings: Civic Offices, smaller offices, theatre, 2 leisure centres
 - Holistic upgrades including building fabric, heat pump, BMS, LED, Solar PV etc.
- **Project Financing:**
 - 35% Client: 39% Pathfinder funding: 26% ESCo
 - NPV of €729k
 - Payback of 8.3 years






PROJECTS- ARTHURSTOWN LANDFILL

Small Scale Solar PV

- **Project Type:** Energy Performance Related Payment (works contract + guarantee clause)
- **Client:** South Dublin County Council
- **Project value:** €275,000 +€27,500
- **Project scope:** ~200kW Small Scale Solar PV
- **Project Financing:**
 - 90% Client : 10% ESCo
 - NPV €243,000



Large Scale Solar PV

- **Project Type:** Feasibility Study
- **Client:** South Dublin County Council
- **Project value:** TBC (approx. €6 mill)
- **Project scope:** ~5 MW Large Scale Solar PV
- **Project Financing:** TBC





PROJECTS- FCC ENERGY SUPPLY CONTRACTS


Solar PV

- **Project Type:** Energy Supply Contract
- **Client:** Fingal County Council
- **Project value:** approx. €460k
- **Project scope:** ~320kW of solar PV on three buildings
- **Project Financing:** TBC



Biomass Boiler

- **Project Type:** Energy Supply Contract
- **Client:** Fingal County Council
- **Project value:** approx. €500k
- **Project scope:** Biomass boilers for 4 buildings
- **Project Financing:** TBC





PROJECTS- MID EAST ENERGY UNIT LEISURE CENTRE UPGRADES

- **Project Type:** Energy Performance Contract
- **Client:** Meath County Council, Kildare County Council and Wicklow County Council
- **Project value:** €3.8 million
- **Project scope:**
 - 7 Leisure Centres (with Swimming Pools)
 - Holistic upgrades including some fabric, heat pump, BMS, LED, Solar PV, etc
- **Project Financing:**
 - 45-50% Client: 30-45% Pathfinder funding: 10-20% ESCo
 - Payback between 10-12 years



Section 04

The Learnings





THE PLAN – BUILD UPON OUR ENPC EXPERIENCE


- Funding Share:
 - €4.3m (**38%**) from the **Private** sector via **ESCos**
 - €5.5m (**48%**) from **grants**
 - €1.6m (**14%**) from the **Local Authority**
- The Plan: Scale up and Expand this Project Delivery Model using **Energy Performance Contracting**






LESSON 1: REVIEWING THE PROJECT PIPELINE

Estimated Direct emissions savings by site (tCO₂/y)






LESSON 1: REVIEWING THE PROJECT PIPELINE





LESSON 1: REVIEWING THE PROJECT PIPELINE


Estimated Direct emissions savings by site (tCO2/y)







LESSON 1: REVIEWING THE PROJECT PIPELINE

Estimated Direct Emissions Reductions by Project (tCO₂/y)






LESSON 2: BUILDING DECARBONISATION STRATEGY





LESSON 3: WHEN TO USE ENPC AND WHEN TO GO TRADITIONAL





LESSON 4: THE CHALLENGES – PROCURING AN ESCO

- It's a mix of:
 - Market **growth** – *Lack of projects*
 - **Contractor** (ESCO) engagement – *Lack of ESCOs*
 - **Supply** and **demand**

Why?

1. The **bid cost risk** has **increased**
2. The **standard EnPC model** no longer works and is **not what the Local Authority needs**



MARKET ENGAGEMENT EVENT



Monday, November 13

Understanding Decarbonisation Pathways for Commercial and Public Buildings

Join us for an insightful event where we explore decarbonisation pathways for commercial and public buildings.

General Admission - 1 +
Free ⓘ
Reserve a spot

- The **Aim**:
 - Understand the **challenges faced by each** stakeholder
- Target **Audience**:
 - Contractors
 - Market Facilitators
 - Building portfolio owners
- The 5 **Big Asks**
- **Interviews** with key stakeholder



LESSON 5: RENOVATION ROADMAP TO ZERO CARBON

An **Energy Performance Contract**:

- Provides the **contract structure** for a **planned, phased decarbonization** of our buildings
- This allows for the **phasing out of existing assets** (boilers, CHPs, etc.) that may be relatively recent installations and have a structured plan for replacement
- **EnPC contractor** (or ESCo) can prepare an **implementation plan** with the building owner so that a **structured investment plan** put in place
- Single **procurement** competition!





ENERGY EFFICIENCY TO DECARBONIZATION



1. Energy Efficiency Project (Leisure Centers)

- CHP, Boilers, BMS controls, LED lighting, Pumps, Fans, etc.

Projected Financial Analysis		Performance Contract
Installation Cost	Client	€299,700 (54%)
	ESCO	€255,300 (46%)
	Grant (Pathfinder)	€ 0
Annual Energy Savings	(kWh)	1,987,092
Annual Energy Cost Savings	(€)	€125,000
Estimated payback	(years)	4.3
Net Present Value	(€)	€410,783



ENERGY EFFICIENCY TO DECARBONIZATION



2. Decarbonization Project (Office Building and Library)

- Heat pump, Windows, Solar PV, BMS controls, LED lighting, Pumps, Fans, etc.

Projected Financial Analysis		Performance Contract
Installation Cost	Client	€ 1,085,000 (35%)
	ESCO	€ 465,000 (15%)
	Grant	€ 1,550,000 (50%)
Annual Energy Savings	(kWh)	1,779,000
Annual Energy Cost Savings	(€)	€ 211,000
Estimated payback	(years)	9.4
Net Present Value	(€)	€ 785,000



ENERGY EFFICIENCY TO DECARBONIZATION



2. Decarbonization Project (Office Building and Library)

- Heat pump, Windows, Solar PV, BMS controls, LED lighting, Pumps, Fans, etc.

Projected Financial Analysis		Performance Contract
Installation Cost	Client	€ 1,085,000 (35%)
	ESCO	€ 465,000 (15%)
	Grant	€ 1,550,000 (50%)
Annual Energy Savings	(kWh)	1,779,000
Annual Energy Cost Savings	(€)	€ 211,000
Estimated payback	(years)	9.4
Net Present Value	(€)	€ 785,000

- Total investment - **€3.1m**
- Windows account for **40%** and have ~90 year payback
- Heat pumps account for **25%** and no cost savings
- Project has **positive NPV**
- But **needs grant aid support**



CONCLUSION AND NEXT STEPS

- 1. Reframe the EnPC message** (from the building owner perspective, Contracted renovation roadmap or pathway to Zero)
- 2. Engage with the ESCo market** (gain a better understanding of the challenges and risk they face and present a better project to the market)
- 3. Reevaluate the pathways for Private Finance** to support our pipeline of projects (not just via the ESCo, recognize the high-cost low-risk measures)
- 4. Further develop the contract selection process** (recognizing the appropriate role of both performance and traditional contract structures)
- 5. Further develop the EnPC contract template** (recognizing the changes in our EnPC model and the staged renovation process, pathway to zero)

Thank You



Joe Hayden, Senior Executive Engineer
Emily Clarke, Energy Engineer